BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

APPROVED SCHEDULE - B

Name of Work: Construction of Compound Wall, Indira canteen Building and Beautification work at Hegadenagara in Ward no. 06

Sl. No.	Approved Qty.	Description	Unit	KRIDL	
				In Figures	In Words
1	392.00	KSRRB 200 Cutting of trees KSRRB 200-1, Cutting of trees girth from 300mm to 600mm including cutting of trunks, branches and removal of stumps stacking of serviceable materials earth filling in the depressions / pit, labour charges complete as per specification . MORTH specification clause 201/chapter 2 NO.No. 136/ Item No. 18.1/ PWD SR 2016-17	Sqm	204.12	Rupees Two Hundred Four And Paise Twelve Only
2	12.83	Dismantling burnt brick masonry in clay mortar / lime mortar / cement mortar and stacking the bricks within a radius of 50 m and removing the debris to a distance upto 200m, No. 268/ Item No. 37.47 PWD SR 2016-17	Cum	168.48	Rupees One Hundred Sixty Eight And Paise Forty Eight Only
3	14.85	Dismantling size stone masonry in clay mortar and stacking the size stone within a radius of 50 m and removing the debris to a distance upto 200m, No. 268/ Item No. 37.48 PWD SR 2016-17	Cum	185.76	Rupees One Hundred Eighty Five And Paise Seventy Six Only
4	81.60	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1,P. No. 5/ Item No. 2.1/ PWD	cum	169.56	Rupees One Hundred Sixty Nine And Paise Fifty Six Only
5	179.55	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123,	Cum	73.36	Rupees Seventy Three And Paise Thirty Six Only
6	122.40	KSRRB M300-53 : Construction of embankment with approved material Gravel/Murrum with all lifts and leads, trasnporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) MORTH Specification No. 305. **(Page No. 144 & Item No. 19.60) PWD SR 2016-17**	Cum	220.32	Rupees Two Hundred Twenty And Paise Thirty Two Only
7	70.26	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications (P.NO -5, I.NO - 2.3, PWD SR 16-17)	Cum	204.12	Rupees Two Hundred Four And Paise Twelve Only
8	27.62	KSRB-4-1.3 : Providing and laying in position **plain cement concrete of mix M 7.5** withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2016-17	cum	5256.36	Rupees Five Thousand Two Hundred Fifty Six And Paise Thirty Six Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer

		Description	Unit	KRIDL	
				In Figures	In Words
	33.06	KSRB 5.2-2 Providing and constructing granite / trap / basalt rubble **stone masonry in foundation** with mud mortar 1:8, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 **Page No. 25/ Item No. 5.5/ PWD SR 2016-17**	cum	4359.96	Rupees Four Thousand Three Hundred Fifty Nine And Paise Ninety Six Only
10	21.00	KSRB 5.3-3 Providing and constructing granite / trap / basalt **size stone masonry in basement with cement mortar 1:6**, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 **Page No. 26/ Item No. 5.9/ PWD SR 2016-17**	cum	5405.40	Rupees Five Thousand Four Hundred Five And Paise Forty Only
11	6.65	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2015-16	cum	5491.80	Rupees Five Thousand Four Hundred Ninety One And Paise Eighty Only
12	42.00	Providing **flush pointing** to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. **Page No. 119/ Item No. 15.1 PWD SR 2016-17**	sqm	104.76	Rupees One Hundred Four And Paise Seventy Six Only
13	70.26	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layers by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour complete as per specifications, specification. (P.NO - 6, I.NO - 2.11, PWD SR 16-17)	Cum	137.16	Rupees One Hundred Thirty Seven And Paise Sixteen Only
14	112.00	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Page No. 24/ Item No. 5.27/ PWD SR 2016-17	Sqm	1011.96	Rupees One Thousand Eleven And Paise Ninety Six Only
15	224.00	KSRB 15.3.10 : Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 110/ Item No. 15.18 / PWD SR 2016-17	Sqm	238.68	Rupees Two Hundred Thirty Eight And Paise Sixty Eight Only
16	224.00	SKSRB 15-16 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to given an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. Page No. 114/ Item No. 15.53.2 / PWD SR 2016-17	Sqm	90.72	Rupees Ninety And Paise Seventy Two Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

12/12
Executive Engineer
12/12

		Description	Unit	KRIDL In Figures	KRIDL In Words
17	33.75	Providing and fixing M.S Gate as per Cheaf Architect Drawing using 50mmX50mm 14 guage M.S hollow pipe frame work bent to ornamental shape as shape as shown in the drawing and 35mmX6mm and 16X16mm squre roads for verticals alternatively spaced at 4cms c/c in two halves and 40mmX6mm M.S flats for horizontal member and at at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of of rust and painted with anti corrosive paint (shop paint) etc., complete the work includes cost of all materials, labour charges for all item of work, hire charges of welding, cutting and grainding equipment, and electricity charges, with lead and lift loading and lunloading charges. etc., complete as per specification and drawing Page No.47/ I No. 7.37/ PWD SR 2016-17	Sqm	3168.72	Rupees Three Thousand One Hundred Sixty Eight And Paise Seventy Two Only
18	52.50	Providing and fixing M.S Gril over existing compound wall as per chief Architect drawing No. 12686, Using 16mm X16mm M.S Sqquare rod at 150mm c/c spacing and 6mmX40mm M.S foats at horizontal and 6mm X12mm M.S flote for ornamental design and providing shop edge design at the vertex of every vertical roads, including welding, grinding wherever necessary. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete the work includes cost of all materials, labour charges for all item of work, hire charges of welding, cutting and grainding equipment, and electricity charges, etc., complete as per specification and drawing Page No.42 / I No. 7.36/ PWD SR	Sqm	5641.92	Rupees Five Thousand Six Hundred Forty One And Paise Ninety Two Only
19	121.10	Providing and fixing Ceramic tiles of size 400x400mm for flooring, threads,steps and landing,laid on a bed of 20mm thick cement morta. 1:3 mix flush pointing with white cement mixed with matching colour pigment including curing, clearing etc. complete .The Worked including curing., clearing etc., complete, The work includes cost of all materials. Labour charges for all items or work, hire charges for equipment, etc., complete as per specification. Page No. 116/ Item No. 14.63 /		1161.00	Rupees One Thousand One Hundred Sixty One Only
20	28.00	KSRB 8.6-5: Providing and fixing in wall surface 2.5 kg/sq.cm H.D.P.E. rain down water pipes 90 mm outer dia approved make and brand with necessary specials like shoes bends and offsets fixed with iron clamps, walls plugs, screws, including cost of materials, labour,Curing complete as per specifications. Page No. 52/ Item No. 8.16/ PWD SR 2016-17	M	429.84	Rupees Four Hundred Twenty Nine And Paise Eighty Four Only

Contractor Signature

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92